




Glen S. Mattioli, Ph.D.

Director of Geodetic Infrastructure and PBO Director





TALK OUTLINE

- Overview of UNAVCO GI program in NSF GAGE Facility
- EarthScope overview: PBO infrastructure, current status, and data products
- Science Drivers and Value of PBO for earthquake and other studies: some examples from AK
- Vision for the future: PBO as a basis for a multi-hazard network of networks across the Americas planned upgrades and enhancements (i.e. new investments) to PBO?
- Sustainability Possible Scenarios and Costs: PBO as a platform to support real-time, multi-hazard monitoring for NOAA and USGS, civil infrastructure, and the commercial sector
- Summary and challenges going forward...



GEODETIC INFRASTRUCTURE UNDER NSF GAGE FACILITY (2013-2018)





The EarthScope Plate Boundary Observatory

Focused, dense deployments of cGPS and strainmeter arrays

- 1100 continuous Global Positioning Systems around tectonic clusters
- 78 borehole tensor strainmeters and 3 component short-period seismometers
- 6 long baseline laser strainmeters
- 25 tiltmeters
- 120 meteorological instruments

Portable GPS receivers

 Pool of 100 portable GPS receivers for temporary deployments to areas not sufficiently covered by continuous GPS

Geo-EarthScope

- InSAR imagery covering the western US
- LIDAR imagery covering the northern and southern San Andreas Fault, Yellowstone Caldera, and faults in Cascadia and Alaska

- Funded by NSF
- Project started in 2003 continues through 2018
- Total EarthScope Budget: ~\$500M over the lifetime of the project


PBO Investment:

• \$100M -Construction Phase (2003-2008)

• \$54M Operations and
Maintenance
Phase I
(2009-2013)

• \$46M -

Operations and Maintenance Phase 2 - GAGE (2014-2018)










PBO: A NUCLEUS FOR A NETWORK OF GEODETIC NETWORKS






















Governance and Community

GAGE Impact

Geodetic Infrastructure


Geodetic Data Services Education & Community Engagement




PBO STATION TYPES IN AK

Strong interest in NASA/ USGS/NOAA earthquake, volcano, and tsunami early warning communities **to upgrade** PBO-AK sites to RT-GPS (I Hz, <I s latency) with accelerometers (MEMS).

Surveying and AK state-wide spatial reference system could also benefit from these upgrades, but appropriate funding partners have yet to be determined.








NON-PBO CGPS ASSETS IN AK


EarthScope PBO geodetic assets make up the vast majority of all cGPS/cGNSS stations in AK.

PBO stations are vital for:


- I) hazard monitoring and early event characterization
- 2) civil infrastructure monitoring
- 3) support of commercial sector for construction, navigation, remote sensing, etc.



Map Date: 2-12-2015. Author: J.Cusick - NPS. Data - CBS base station list from Trimble 2-1-2015. Modified with CORS MAP. Other data sources - NPS, DOT roads and airports




THE PLATE BOUNDARY OBSERVATORY IN ALASKA HIGHLIGHTS FROM 2003-2015







- Before the PBO came to Alaska in 2003, fewer than 5 continuous GPS reference stations were operating in Alaska with reliable telemetry.
- Today, 140 PBO stations in Alaska provide reliable, continuous access to GPS, tiltmeter, and meteorologic data.
- PBO sites installed prior to 2006 eruption of Augustine Volcano.
- Since 2003, UNAVCO has spent \$30M on PBO-Alaska network construction and operations/maintenance (\$2.5M/yr).
- Alaska-based UNAVCO staff (currently 3.5 FTE, as many as 6 FTE during construction phase), located in Anchorage and Fairbanks.
- ~80 field visits per year required to maintain the PBO Alaska network.
- •UNAVCO has a proven record of success in Alaska: PBO construction and maintenance has been completed safely, on-schedule, and within budget.













Cumulative data return for the PBO network since the beginning of the GAGE O&M period (FY2014) is:

96% for GPS/Met
99% for seismic
99% for BSM
100% for LSM
94% for pore pressure
91% for tilt









Cumulative data return for the PBO network since the beginning of the GAGE O&M period (FY2014) is:

96% for GPS/Met
99% for seismic
99% for BSM
100% for LSM
94% for pore pressure
91% for tilt








Cumulative data return for the PBO network since the beginning of the GAGE O&M period (FY2014) is:

96% for GPS/Met
99% for seismic
99% for BSM
100% for LSM
94% for pore pressure
91% for tilt




GAGE Processing Centers - Positioning Data Quality





GAGE Processing Centers - Positioning Data Quality





THE PLATE BOUNDARY OBSERVATORY IN ALASKA SCIENCE AND OTHER DRIVERS






- Tectonic block definition and motion examination of oblique convergence and slip partitioning
- Strain accumulation and locking along the megathrust interface between NAM-PAC
- Post-seismic visco-elastic response from the 1964 M9.2 Anchorage and 2002 Mw7.9 Denali earthquakes
- Static and dynamic forcing of volcanic systems and changes in state of from seismic- and ice-loading
- Short to medium-term characterization of crustal magma dynamics and volcanic eruptions (e.g. dike intrusion and propagation)
- Support of hazard missions of USGS and NOAA EEW/TEW and NGS CORS - PBO AK contributes 76 of ~100 stations
- With deployment of USArray in AK integration of crustal and lithospheric structure with surface deformation field




THE PLATE BOUNDARY OBSERVATORY IN ALASKA HIGHLIGHTS FROM 2003-2015






AK SHIELD EXERCISE REPLAY OF M9.2 MARCH 27, 1964 EARTHQUAKE


Epicenter and rupture area



Horizontal coseismic



Vertical coseismic





Data from M9.2 1964 event (Suito and Freymueller, JGR, 2009) was used to drive 2014 AK Shield simulation for NASA READI prototype earthquake early warning system



NASA READITEAM PRODUCTS FOR AK SHIELD

JPL tsunami simulations based on RT-GPS (1 Hz) coseismic displacements for M9.2 1964-type event (FFM of Suito and Freymueller, JGR, 2009






NASA READI team: JPL, UCSD-SIO, CWU with PBO as key data provider



GAGE: RT-GPS/GNSS UPGRADE PLAN






Governance and Community

GAGE Impact Geodetic Infrastructure


Geodetic Data Services Education & Community Engagement



GAGE: RT-GPS/GNSS UPGRADE PLAN







Governance and Community


GAGE Impact Geodetic Infrastructure

Geodetic Data Services Education & Community Engagement



GAGE: RT-GPS/GNSS UPGRADE PLAN

700





Real-Time Stations


Governance and Community

GAGE Impact Geodetic Infrastructure

Geodetic Data Services Education & Community Engagement




PBO REAL-TIME GPS/GNSS USERS



ABOVE: Based on the NUMBER OF NEW USERS (new requestors) per year, the percentage of commercial users relative to academic and agency users has increased consistently over the past four years.

BELOW: Based on the VOLUME OF DATA DOWNLOADED per year, the percentage of commercial users relative to academic users has decreased consistently over the past several years.

Interpretation: there are more commercial users than academic users of RTGPS data, but academic users access larger volumes of data.




Trends in PBO RT-GPS usage:


Increase in the number of new commercial sector users from 2010 to 2013

Increase in the amount of RT-GPS data downloaded by academic groups




RT-GPS - CURRENT NETWORK








RT-GPS - CURRENT NETWORK






RT-GPS - CURRENT NETWORK






RT-GPS: WHAT COULD BE DONE WITH PBO-AK UPGRADES

Network Background – Seismic & hr-GPS



Test Case: 2016 Mw7.1 Iniskin, Alaska From R. Grapenthin et al. (ms. in prep)

Processing Strategy




This is GPS only - not a seismogeodetic combination



RT-GPS: WHAT COULD BE DONE WITH PBO-AK UPGRADES

PGD – Magnitude evolution

Better estimate of PGD in ~60 s!




Based on Crowell et al. (2013), Melgar et al. (2015) developed a scaling relationship to infer Mw from PGD & hypocentral distance (R):

log(PGD) = A + B*Mw + C*Mw*log(R)

Test Case: 2016 Mw7.1 Iniskin, Alaska From R. Grapenthin et al. (ms. in prep)

PGD – Subnet




This is GPS only - not a seismogeodetic combination




RT-GPS: WHAT COULD BE DONE WITH PBO-AK UPGRADES

Emerging technique exploiting Doppler shift of L1 or L2 GPS phase observable to create **velocigrams** - no 'positioning' estimation needed...



Test Case: 2016 Mw7.1 Iniskin, Alaska From R. Grapenthin et al. (ms. in prep)





FUTURE GEOPHYSICAL FACILITIES WORKSHOP

Workshop held in May 2015 in Leesburg, VA > 100 participants


- Report divides into three components related to US NSF-funded geophysical & seismo-geodetic facilities:
 - Existing Foundational

Maintained permanent seismic, strainmeter, and geodetic networks

- A global very broadband seismographic network
- Permanent and continuously recording GPS (GNSS) networks
- A network of borehole strainmeters
- Emergent Foundational

Development of operational RT-GNSS processing at >1 Hz

Frontier






POST SAGE-GAGE VISION - SOME KEY PBO ISSUES

For example, the community envisions a future that includes:

- (I) near-real-time and daily maps of deformation derived from integrated seismic, Global Navigation Satellite System (GNSS) instrumentation, and orbiting radar satellite data;
- (2) anchored and drifting seafloor and water column geophysical instrumentation distributed around the globe;
- (3) arrays of fiber optic cables providing spatially continuous high-rate sampling of surface strain;
- (6) global telemetry providing high-rate and low-latency sampling from any number of remote instruments; and
- (7) routine access to high performance computing (HPC) and associated capabilities for data reduction and model inference on an unprecedented scale.




- Total of 19 L2C-capable SVs in orbit now
- Total of I2 L5-capable SVs in orbit now
- Block III SVs available for launch in 2016
- DoD/DoC announced phase-out of civil access to P(Y) on L1/L2 effective 2020 to drive commercial sector to L2C/L5 applications
 - PBO has ~900 Trimble NetRS deployed only can encode L2C & no GNSS signals (all are EOL/EOS); most EAR/PLR pool receivers are the same obsolete, legacy technology
 - PBO/COCONet/TLALOCNet has ~250 Trimble NetR9 deployed
 can encode L2C, L5, +GNSS; PBO turned on GLONASS at 140 stations
- UNAVCO selected Septentrio as its GNSS receiver
 preferred vendor. We have purchased and deployed 120 (PBO + ODOT) new PolaRx5 instruments in 2016.






- Total of 19 L2C-capable SVs in orbit now
- Total of I2 L5-capable SVs in orbit now
- Block III SVs available for launch in 2016
- DoD/DoC announced phase-out of civil access to P(Y) on L1/L2 effective 2020 to drive commercial sector to L2C/L5 applications
 - PBO has ~900 Trimble NetRS deployed only can encode L2C & no GNSS signals (all are EOL/EOS); most EAR/PLR pool receivers are the same obsolete, legacy technology
 - PBO/COCONet/TLALOCNet has ~250 Trimble NetR9 deployed
 can encode L2C, L5, +GNSS; PBO turned on GLONASS at 140 stations
- UNAVCO selected Septentrio as its GNSS receiver
 preferred vendor. We have purchased and deployed 120 (PBO + ODOT) new PolaRx5 instruments in 2016.






- Total of 19 L2C-capable SVs in orbit now
- Total of I2 L5-capable SVs in orbit now
- Block III SVs available for launch in 2016
- DoD/DoC announced phase-out of civil access to P(Y) on L1/L2 effective 2020 to drive commercial sector to L2C/L5 applications
 - PBO has ~900 Trimble NetRS deployed only can encode L2C & no GNSS signals (all are EOL/EOS); most EAR/PLR pool receivers are the same obsolete, legacy technology
 - PBO/COCONet/TLALOCNet has ~250 Trimble NetR9 deployed
 can encode L2C, L5, +GNSS; PBO turned on GLONASS at 140 stations
- UNAVCO selected Septentrio as its GNSS receiver
 preferred vendor. We have purchased and deployed 120 (PBO + ODOT) new PolaRx5 instruments in 2016.





- Total of 19 L2C-capable SVs in orbit now
- Total of I2 L5-capable SVs in orbit now
- Block III SVs available for launch in 2016
- DoD/DoC announced phase-out of civil access to P(Y) on L1/L2 effective 2020 to drive commercial sector to L2C/L5 applications
 - PBO has ~900 Trimble NetRS deployed only can encode L2C & no GNSS signals (all are EOL/EOS); most EAR/PLR pool receivers are the same obsolete, legacy technology
 - PBO/COCONet/TLALOCNet has ~250 Trimble NetR9 deployed
 can encode L2C, L5, +GNSS; PBO turned on GLONASS at 140 stations
- UNAVCO selected Septentrio as its GNSS receiver
 preferred vendor. We have purchased and deployed 120 (PBO + ODOT) new PolaRx5 instruments in 2016.






UPGRADES TO PBO INSTRUMENTS




UPGRADES TO PBO INSTRUMENTS





UPGRADES TO PBO INSTRUMENTS






PBO: STATION IN AK - DESIGN AND CHALLENGES





GPS NETWORK UPTIME


Operational definition: a GPS station is considered "up" if less than 3 days have passed since data arrived in the UNAVCO archive






GPS NETWORK UPTIME

Operational definition: a GPS station is considered "up" if less than 3 days have passed since data arrived in the UNAVCO archive






Sept 2018 (est.)




OPERATIONS AND MAINTENANCE COSTS: CONUS AND AK





100 MOST EXPENSIVE STATIONS





OPERATIONS AND MAINTENANCE: STATION PRIORITIZATION PLAN

GPS/GNSS stations will be prioritized into three categories based on the science goals and the number and diversity of stakeholder interests, guided by advisory committees and community:

- 1) highest problems will receive attention and remediated as rapidly as possible;
- 2) intermediate problems will be diagnosed and will receive attention as resources permit;
- 3) *lowest* problems will be diagnosed, but any required service will only occur if periodic maintenance is scheduled for that station during the upcoming annual field season.

Under GAGE, engineers visited each station approximately every five years for scheduled battery and hardware maintenance and unscheduled maintenance was performed on a best-effort basis. *Our new O&M model will allow more efficient use of available resources*, and most importantly, focus them on the stations that are deemed the highest priority by stakeholders.

UNAVCO

CURRENT PBO CAPABILITIES IN AK

NSF EarthScope Plate Boundary Observatory Network in Alaska:

Real-time capabilities and potential:

GPS - NetRS (129)


GNSS - NetR9 (8) - GLONASS only

GNSS - PolaRx5 (3) - all SVs

RT - PIVOT (13)

RT - BKG (34)

Metpacks (2)






ONE SCENARIO FOR PBO ENHANCEMENT

Example Scenario:

Tsunami Early Warning sensor network for constraining earthquake source parameters:

a straw-man plan to upgrade to 30 real-time stations proximal to the subduction interface to support NOAA-NTWC, USGS, and AEC hazard missions



UNAVCO has a proposal pending at NOAA


UNAVCO


ONE SCEN

Example Scenario:


Tsunami Early Warning sensor network for constraining earthquake source parameters:


a straw-man plan to upgrade to 30 real-time stations proximal to the subduction interface to support NOAA-NTWC, USGS, and AEC hazard missions





Example TsEW subset (total = 30 sites





- Current RT sites with latencies < 1 s</p>
- Test RT (BKG) sites /w good latencies

-140°

- Minor work needed
- Moderate work needed
- Major work needed
- Unlikely Candidate

-180°

UNAVCO has a proposal pending at NOAA



ONE SCENARIO FOR PBO ENHANCEMENT

- Budget includes one time costs to upgrade 30 key stations, staffing and development and set up of local monitoring.
- Annual costs include staffing for near-real-time monitoring, triage, and responding to station outages, associated travel, and all recurring communications costs with satellite uplink failover.

	One Time	Annual
Salaries	\$328,194	\$88,317
Fringe	\$189,171	\$50,906
Materials/Supplies	\$398,820	\$10,000
Helicopter Services, etc.	\$315,000	\$50,000
Travel	\$101,003	\$20,000
Other Direct Costs	\$107,790	_
Communications	\$456,000	\$456,000
Total Direct Costs	\$1,895,978	\$675,223
Indirect Costs	\$304,494	\$108,441
Total	\$2,200,472	\$783,663



TYPICAL PBO AK STATION - CURRENT STATE

Standard PBO GPS Site

upgrade

Real-time PBO GNSS Site






Lower-bandwidth telemetry designed for daily downloads of standard 15-sec frequency, GPS-only data


Standard PBO GPS Site

Current PBO station





Upgraded PBO station





PBO: A CRITICAL NATIONAL AND AK RESOURCE: SUMMARY OF IMPORTANT CONCERNS

Aging PBO infrastructure - planned replacement in GAGE, not fully possible under current budget scenarios. Many EOL/EOS units will remain in place at close of GAGE Facility. Reduced O&M for PBO means possible loss of data and likely will decrease up-time in long-run. Future post-GAGE (under NGEO) is uncertain...

Need for **high-rate and real-time data streams** and archived products to position UNAVCO for future (NSF and non-NSF) funding and relevance. **PBO is now viewed as a "utility" by many critical stakeholders.** Cost to renew and upgrade selected PBO-AK stations to real-time would be considerable (\$2.2M one-time funds and \$0.8M/yr ongoing costs using current technologies).

- · Geodetic Infrastructure is vital to multiple communities and agencies how will it be sustained?
- NSF (and NASA/USGS to a lesser degree) has made the **initial investment** but the need for **sustaining federal and state partners** remains paramount...

Impact of loss (possible descoping by NSF) or degradation of PBO assets (physical and human) stakeholders are charged with Safety of Life warnings, Initial Crisis Response, and development and maintenance of state-wide Spatial Reference Network systems needs evaluation and mitigation.



QUESTIONS?

